KADUR DIVISION.

Dated 16th July 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 15th August 1904, for constructing a new sandal koti at Chikmagalur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1905.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified, will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new sandal koti at Chikmagalur;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantities of estimate for sandal koti at Chikmagalur :—

Items of work.	*Per.*	*quantity.*
Earthwork, excavation and filling between basement	C. yds.	254
Burnt stone with bond slabs in lime mortar, foundations and basement	C. ft.	11,876
Burnt brick in lime mortar, superstructure	C. ft.	24,483
Do. do. arch work	C. ft.	47
Burnt stone slabs, dressed	S. ft.	839
Plastering with lime plaster	Sqr.	336·27
White-washing, 2 coats	Sqr.	251·73
Color washing, 2 do	Sqr.	84·54
Flooring with 1st class Mangalore tiles on 6" sand bedding and cement pointing.	Sqr.	29·69
Flooring with gravel including carting and tamping	C. yds.	173
Teakwood work wrought and put up	C. ft.	2,062
Do eave board, ornamental	R. ft.	1,220
Roofing with 1st class Mangalore tiles and teak reepers, etc., complete.	Sqr.	79·54
Roofing with teak reepers on two course of flat and Mangalore tiles, fixing the same in fine lime mortar.	Sqr.	112·34
Ridge tiles set in mortar	R. ft.	607
Roofing with corrugated zinc sheet with teak reepers, etc., complete.	Sqr.	21·60
Zinc valley	R. ft.	64
Teakwood doors pannelled with iron works, rim lock, etc., complete	S. ft.	364
Do window pannelled and glazed with iron works and iron bars, etc., complete.	"	160
Teakwood glazed ventilators with iron bars, etc., complete	"	24
Chocolate painting	Sqr.	23·00
Wood oiling	"	200
Teakwood entrance gate with iron works, etc., complete (as per plan)	S. ft.	84
Cornice work	R. ft.	600
Clearing site and forming drainage	Rs.	Lump sum.
Iron works for king posts, Truss as per detail	lbs.	2,457
Do bolts and nuts do	Each	358

N. B.—Timber required will be supplied by Forest Department free of cost in the Forest but the carriage and conversion should be undertaken by the contractor.

213

Dated 16th July 1904.

1. Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur Division, up to 15th August 1904, for constructing a new sandal koti at Tarikere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1905.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new sandal koti at Tarikere," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Approximate quantities of estimate for sandal koti at Tarikere :—

Items of work.	*Per*	*Quantity.*
Earthwork, excavation and filling in basement	C.yd.	216
Burnt stone with bond slabs in lime mortar, foundation and basement ...	C.ft.	10,067
Burnt brick in lime mortar, superstructure	„	20,873
Do arch work	„	47
Burnt stone slabs dressed	S.ft.	693
Plastering with lime plaster	Sqr.	282·54
Whitewashing, 2 coats	„	210·00
Color do	„	72·53
Flooring with 1st class Mangalore tiles on 6" sand bedding and cement pointing.	„	29·69
Do gravel including carting and tamping	C. yd.	134
Teakwood work wrought and put up	C. ft.	1,591
Do eave board, ornamental	R.ft.	1,022
Roofing with 1st class Mangalore tiles and teak reepers, etc., complete..	Sqr.	79·02
Do teak reepers on two course of flat and Mangalore tiles, fixing the same in fine lime mortar.	„	76·34
Ridge tiles set in mortar	R.ft.	507
Roofing with corrugated zinc sheet with teak reepers, etc., complete ..	Sqr.	21·60
Zinc sheet for valley	R.ft.	64
Teakwood doors pannelled with iron work, rim lock, etc., complete ..	S.ft.	308
Do windows pannelled and glazed with iron work and iron bars, etc., complete.	„	160
Do glazed ventilators with iron work and bars, etc., complete ...	„	18
Chocolate painting	Sqr.	20·67
Wood oiling	„	180·00
Teakwood entrance gate with iron works, etc., (as per plan) ...	S.ft.	84
Cornice work	R.ft.	600
Clearing site and forming drainage	Rs.	L. S.
Iron works for king posts, Truss as per detail	lbs.	1,394
Do iron nuts and bolts do	Each	258

N. B.—Timber required will be supplied by Forest Department in the Forest, free of cost, but carriage and conversion should be undertaken by the contractor.

H. J. MOLLOY, *Executive Engineer.*

2 G